

GENERAL SUMMARY				
Project Name:		0		
Project ID:				
Scope:		Drywall and Paint		
BUILDING GSF				
DIVISION NO.		DESCRIPTION	TOTAL DIV. COST	TOTAL DIV. COST (PER SF)
1000	GENERAL REQUIREMENTS		\$ 1,000	#DIV/0!
2000	EXISTING CONDITIONS		\$ 3,558	#DIV/0!
9000	FINISHES		\$ 38,015	#DIV/0!
2600	ELECTRICAL		\$ 2,304	#DIV/0!
TOTAL TRADE COST			\$ 42,573	#DIV/0!
OVERHEAD AND PROFIT		15%	\$ 6,385.91	#DIV/0!
INSURANCE		2%	\$ 639	#DIV/0!
CONTINGENCY		0%	\$ -	#DIV/0!
TAX		5%	\$ 1,916	#DIV/0!
SUGGESTED BID			\$ 51,513	#DIV/0!

DETAILED BREAKDOWN OF ITEMS													
Project Name:													
Project ID:													
Scope: Drywall and Paint													
												Date:	6-Mar-25
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
GENERAL REQUIREMENTS													
1			Permits	LS	1	0%	1	0.000	\$ 50.00	\$ -	\$ -	\$ -	\$ -
2			Supervision and Coordination	LS	1	0%	1	0.000	\$ 50.00	\$ -	\$ -	\$ -	\$ -
3			Submittals and Shop drawings	LS	1	0%	1	0.000	\$ 50.00	\$ -	\$ -	\$ -	\$ -
4			Final Cleaning	LS	1	0%	1	0.000	\$ 50.00	\$ -	\$ -	\$ -	\$ -
5			Mobilization Costs	LS	1	0%	1	0.000	\$ 50.00	\$ -	\$ -	\$ -	\$ -
6			Temporary Control & Facilities	LS	1	0%	1	20.000	\$ 50.00	\$ 1,000.00	\$ -	\$ 1,000.00	\$ 1,000
7			Scaffolding	LS	1	0%	1	0.000	\$ 50.00	\$ -	\$ -	\$ -	\$ -
												SUBTOTAL \$	1,000
FINISHES													
DRYWALL													
			One Layer of 1/2" Gypsum Board @ Wall	SF	292								
8			No of Sheets (4x8)	EA	10	0%	10	0.557	\$ 55.70	\$ 31.01	\$ 15.84	\$ 46.85	\$ 470
9			Tapping	LF	146	10%	161	0.011	\$ 55.70	\$ 0.62	\$ 0.02	\$ 0.64	\$ 103
10			Joint Compound	LBS	38	10%	42	0.075	\$ 55.70	\$ 4.18	\$ 0.50	\$ 4.68	\$ 195
11			Screws	EA	482	0%	482	0.050	\$ 55.70	\$ 2.79	\$ 0.02	\$ 2.81	\$ 1,351
			One Layer of 1/2" Gypsum Board @ Ceiling	SF	580								
12			No of Sheets (4x8)	EA	20	0%	20	0.557	\$ 55.70	\$ 31.01	\$ 15.84	\$ 46.85	\$ 934
13			Tapping	LF	290	10%	319	0.011	\$ 55.70	\$ 0.62	\$ 0.02	\$ 0.64	\$ 204
14			Joint Compound	LBS	75	10%	83	0.075	\$ 55.70	\$ 4.18	\$ 0.50	\$ 4.68	\$ 388
15			Screws	EA	957	0%	957	0.004	\$ 55.70	\$ 0.22	\$ 0.02	\$ 0.24	\$ 232
PAINT FINISHES													
16			Paint @ Wall	SF	292	10%	321	0.046	\$ 55.70	\$ 2.56	\$ 0.40	\$ 2.96	\$ 951
17			Paint @ Ceiling	SF	580	10%	638	0.046	\$ 55.70	\$ 2.56	\$ 0.40	\$ 2.96	\$ 1,890
FLOOR FINISHES													
18			Water Proof Flooring	SF	1734	10%	1907	0.048	\$ 55.70	\$ 2.67	\$ 1.92	\$ 4.59	\$ 8,746
WALL BASE													
19			3 1/2" Base Board	LF	122	10%	134	0.046	\$ 55.70	\$ 2.58	\$ 2.74	\$ 5.32	\$ 715
												SUBTOTAL \$	16,180
												PROJECTED COST	
												\$17,180	
												OVERHEAD AND PROFIT	15%
												INSURANCE	2%
												CONTINGENCY	0%
												TAX	4.5%
												SUGGESTED BID	
												\$20,787	

DETAILED BREAKDOWN OF ITEMS													
Project Name:													
Project ID:													
Scope: Drywall and Paint													
												Date:	6-Mar-25
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
GENERAL REQUIREMENTS													
1			Permits	LS	1	0%	1	0.000	\$ 50.00	\$ -	\$ -	\$ -	\$ -
2			Supervision and Coordination	LS	1	0%	1	0.000	\$ 50.00	\$ -	\$ -	\$ -	\$ -
3			Submittals and Shop drawings	LS	1	0%	1	0.000	\$ 50.00	\$ -	\$ -	\$ -	\$ -
4			Final Cleaning	LS	1	0%	1	0.000	\$ 50.00	\$ -	\$ -	\$ -	\$ -
5			Mobilization Costs	LS	1	0%	1	15.000	\$ 50.00	\$ 750.00	\$ -	\$ 750.00	\$ 750
6			Temporary Control & Facilities	LS	1	0%	1	25.000	\$ 50.00	\$ 1,250.00	\$ -	\$ 1,250.00	\$ 1,250
7			Scaffolding	LS	1	0%	1	0.000	\$ 50.00	\$ -	\$ -	\$ -	\$ -
												SUBTOTAL \$	2,000
EXISTING CONDITIONS													
8			Remove Existing Brown Wall Panel	SF	705	0%	705	0.018	\$ 48.64	\$ 0.88	\$ -	\$ 0.88	\$ 617
9			Remove Existing Flooring	SF	1591	0%	1591	0.013	\$ 48.64	\$ 0.63	\$ -	\$ 0.63	\$ 1,006
10			Remove Existing Ceiling Tiles	SF	1591	0%	1591	0.025	\$ 48.64	\$ 1.22	\$ -	\$ 1.22	\$ 1,935
												SUBTOTAL \$	3,558
FINISHES													
DRYWALL													
			One Layer of 1/2" Gypsum Board @ Wall	SF	705								
11			No of Sheets (4x8)	EA	24	0%	24	0.557	\$ 55.70	\$ 31.01	\$ 15.84	\$ 46.85	\$ 1,135
12			Tapping	LF	353	10%	388	0.014	\$ 55.70	\$ 0.78	\$ 0.02	\$ 0.79	\$ 308
13			Joint Compound	LBS	92	10%	101	0.075	\$ 55.70	\$ 4.18	\$ 0.50	\$ 4.68	\$ 472
14			Screws	EA	1163	0%	1163	0.006	\$ 55.70	\$ 0.33	\$ 0.02	\$ 0.35	\$ 412
			One Layer of 1/2" Gypsum Board @ Ceiling	SF	1591								
15			No of Sheets (4x8)	EA	55	0%	55	0.557	\$ 55.70	\$ 31.01	\$ 15.84	\$ 46.85	\$ 2,562
16			Tapping	LF	796	10%	875	0.014	\$ 55.70	\$ 0.78	\$ 0.02	\$ 0.79	\$ 695
17			Joint Compound	LBS	207	10%	228	0.075	\$ 55.70	\$ 4.18	\$ 0.50	\$ 4.68	\$ 1,064
18			Screws	EA	2625	0%	2625	0.006	\$ 55.70	\$ 0.33	\$ 0.02	\$ 0.35	\$ 930
PAINT FINISHES													
19			Paint @ Wall	SF	705	10%	776	0.020	\$ 49.10	\$ 0.98	\$ 0.40	\$ 1.38	\$ 1,072
20			Paint @ Ceiling	SF	1591	10%	1750	0.020	\$ 49.10	\$ 0.98	\$ 0.40	\$ 1.38	\$ 2,419
FLOOR FINISHES													
21			Water Proof Flooring	SF	1591	10%	1750	0.041	\$ 55.70	\$ 2.30	\$ 1.92	\$ 4.22	\$ 7,381
WALL BASE													
22			3 1/2" Base Board	LF	141	10%	155	0.040	\$ 55.70	\$ 2.23	\$ 2.74	\$ 4.97	\$ 771
												SUBTOTAL \$	19,221
ELECTRICAL													
LIGHT FIXTURES													
23			Ceiling Lights	EA	12	0%	12	1.100	\$ 89.00	\$ 97.90	\$ 94.12	\$ 192.02	\$ 2,304
												SUBTOTAL \$	2,304

DETAILED BREAKDOWN OF ITEMS

Project Name:

Project ID:

Scope: Drywall and Paint

Date: 6-Mar-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
PROJECTED COST													\$27,084
OVERHEAD AND PROFIT											15%	\$4,063	
INSURANCE											2%	\$406	
CONTINGENCY											0%	\$0	
TAX											4.5%	\$1,219	
SUGGESTED BID													\$32,771

DETAILED BREAKDOWN OF ITEMS													
Project Name:													
Project ID:													
Scope: Drywall and Paint													
												Date:	6-Mar-25
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
GENERAL REQUIREMENTS													
1			Permits	LS	1	0%	1	0.000	\$ 50.00	\$ -	\$ -	\$ -	\$ -
2			Supervision and Coordination	LS	1	0%	1	0.000	\$ 50.00	\$ -	\$ -	\$ -	\$ -
3			Submittals and Shop drawings	LS	1	0%	1	0.000	\$ 50.00	\$ -	\$ -	\$ -	\$ -
4			Final Cleaning	LS	1	0%	1	0.000	\$ 50.00	\$ -	\$ -	\$ -	\$ -
5			Mobilization Costs	LS	1	0%	1	0.000	\$ 50.00	\$ -	\$ -	\$ -	\$ -
6			Temporary Control & Facilities	LS	1	0%	1	10.000	\$ 50.00	\$ 500.00	\$ -	\$ 500.00	\$ 500
7			Scaffolding	LS	1	0%	1	0.000	\$ 50.00	\$ -	\$ -	\$ -	\$ -
												SUBTOTAL \$	500
FINISHES													
DRYWALL													
			One Layer of 1/2" Gypsum Board @ Wall	SF	92								
8			No of Sheets (4x8)	EA	3	0%	3	0.557	\$ 55.70	\$ 31.01	\$ 15.84	\$ 46.85	\$ 148
9			Tapping	LF	46	10%	50	0.011	\$ 55.70	\$ 0.62	\$ 0.02	\$ 0.64	\$ 32
10			Joint Compound	LBS	12	10%	13	0.075	\$ 55.70	\$ 4.18	\$ 0.50	\$ 4.68	\$ 61
11			Screws	EA	151	0%	151	0.050	\$ 55.70	\$ 2.79	\$ 0.02	\$ 2.81	\$ 425
PAINT FINISHES													
12			Paint @ Wall	SF	92	10%	101	0.046	\$ 49.10	\$ 2.26	\$ 0.40	\$ 2.66	\$ 269
FLOOR FINISHES													
13			Water Proof Flooring	SF	323	10%	355	0.033	\$ 55.70	\$ 1.84	\$ 1.92	\$ 3.76	\$ 1,335
WALL BASE													
14			3 1/2" Base Board	LF	69	10%	76	0.032	\$ 55.70	\$ 1.78	\$ 2.74	\$ 4.52	\$ 343
												SUBTOTAL \$	2,614
												PROJECTED COST	
												OVERHEAD AND PROFIT	\$3,114
												INSURANCE	\$467
												CONTINGENCY	\$0
												TAX	\$140
												SUGGESTED BID	\$3,768